ICL Pathway 100 Trial Surveys Report Ref: IM/REP/029

Version: 1.0 Date: 2/03/98

Document Title: 100 Trial Surveys Report

Document Type: Report

Abstract: This report details the results of the 100 offices surveyed to

analyse the impact of new options for preparing the post offices

for the national rollout.

Status: Report

Distribution: ICL POCL

Tony Oppenheim Dave Miller
Liam Foley Bruce McNiven

Mike Coombs
Barrie Davies
Bob McDermott
Douglas Craik
Andy Jones
Mike Hauxwell

Mark Fisk Library

Author: Barry Hancill / Billy Herd

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

0 Document control

0.1 Document history

Version	Date	Reason
1.0	02/03/98	Report issued

0.2 Approval authorities

Not applicable

0.3 Associated documents

Reference	Versi	Date	Title	Source
	on			
IM/REQ/005	1.0	24/02/98	Horizon Counter Infrastructure Rollout - Survey Requirements Specification	M. Fisk

0.4 Abbreviations

WTplc Workplace Technologies plc

0.5 Changes in this version

First issue

100 Trial Surveys Report

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

0.6 Table of content

1. Introduction
2. Scope
3. Management Summary
4. Surveys
4.1 The survey teams
4.2 Training
4.3 Survey review
5. Results of the Survey
5.1 Outlet Categories
5.2 Cost Yreakdown
5.3 Stands
5.4 Utilisation of Stands
6. No solution offices 12
7. Additional Options 13
7.1 Result of the review of additional options
7.2 Flat Screen Monitor13
7.3 Seats
7.4 Extending the Reach Parameters14
7.5 Expanding the Reach Parameters
7.6 Self Inking Date Stamps14
8 Other Findings

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

1. Introduction

The post implementation review of Horizon in the release 1b post offices, undertaken by POCL, suggested that certain Horizon components were not most efficiently located for frequent and repetitive use. As a result POCL commissioned an ergonomic study of the Horizon equipment in use at certain post offices in the South West Region and from this review provided parameters to ICL Pathway to be used when installing equipment.

As it was unknown whether this change would have a material effect on the cost of preparation work a joint effort has been undertaken to survey 100 outlets following the new parameters. This report provides a breakdown of the results into the following categories:

- standard office preparations
- standard office preparations with stands or shelves
- office modifications (re-survey for screen/counter modifications)
- · no solution offices
- impact of additional options

In addition this report covers any other issues that have been raised during this exercise.

2. Scope

The 100 post offices visited have been specifically chosen as a representative sample of the POCL estate. 80 were chosen from the offices currently operating the Horizon platform (Live offices). The remaining 20 represent the larger branch offices and those already with automation i.e. ECCO outlets.(New offices) ¹

For the purpose of this exercise it has been assumed that we are visiting the office for the first time. The prices quoted reflect the total cost incurred to prepare the office in accordance with the ergonomic parameters and where necessary, previous documentation has been reviewed to determine the extent of work already undertaken. If previous work is part of the proposed solution the associated cost is included in the total office cost. Where it is not it is excluded.

¹ 4 offices were excluded from the Release 1B rollout as the cost of office modification was too great. This means that the most expensive offices to prepare are missing from the 80 sampled. The average

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

For example, in the majority of offices the cost of Image monitor stands have been removed as they will become redundant when the final solution is implemented. In offices where they will be utilised for another purpose, the cost has been included.

Likewise, it should not be assumed that the costs associated with the 80 existing offices reflect the cost of upgrade to the ergonomic standard. In some instances extra costs will be incurred in rectifying work already undertaken.

The cost of resurvey visits have been included where appropriate.

The Site Survey Requirements document, (Ref. [1]) was modified to reflect the parameter changes and this together with the survey and resurvey processes were agreed by both parties prior to the surveys taking place. In addition five different types of monitor / keyboard stands, some of which are still undergoing ergonomic evaluation, were considered. For all outlets that required a re-survey or offices where no solution could be found, the following additional options were considered:

- POCL approved seating
- · a flat screen monitor
- extension of the reach parameters defined in the ergonomic study

The use of a separate smart card reader was to be considered but this was discounted during discussions on agreeing the Site Survey Requirements document as its use created further operational difficulties.

The impact of using these additional options is covered in section 7.

3. Management Summary

Of the 100 offices surveyed, 18 were classified as no solution offices. With an estate of 19,088 offices (excluding Cash Remittance Units) this would equate to 3,435 offices nationally.

For the remaining 82 offices costs have been split into:

- Site preparation costs including stands Cost X
- Additional costs Cost Y

Cost apportionment to allow the compilation of summary costs is defined in Appendix A, but it is understood that reapportionment of some costs may take place following joint discussions.

No of offices	Cost X (£)	Cost Y (£)	total cost (£)
82	92,157.57	82,237.18	174,394.75

This gives an average cost per office of:

Cost X (£)	Cost Y (£)	total cost (£)
1,123.87	1,002.89	2,126.76

By subtracting the no solution offices from the total estate of 19,088, the remainder of the estate which could be modified to accept Horizon is 15,653. This would give a total cost of:

No of offices	Cost X (£)	Cost Y (£)	total cost (£)
15,653	17,591,937.11	15,698,237.17	33,290,174.28

Recognising the inherent complications with this argument, propagating the average cost across the whole estate would yield the following figures:

No of offices	Cost X (£)	Cost Y (£)	total cost (£)
19,088	21,452,430.56	19,143,164.32	40,595,594.88

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

Costs quoted exclude Value Added Tax.

There has been no contingency allowed for any inconsistencies in the sample chosen.

No allowance has been made for any potential savings which could be expected from competitively tendering for the shopfitting work.

4. Surveys

4.1 The survey teams

Due to the tight timescales involved in providing this report it was necessary for the survey and resurvey processes to be conducted in a single visit.

The survey teams consisted of a Pathway surveyor with responsibility for completion of the survey process, and a POCL surveyor to consider counter and screen modifications where a resurvey was necessary. It was also felt that joint attendance provided a check and balance to the process and would reduce the chance of solutions being more involved than absolutely necessary.

It should be noted that neither attendees were qualified joiners and as a result some solutions proposed could later be found to be either more expensive than estimated, or impractical to achieve. Similarly there were some solutions which involved relocating safes within the secure area of the Post Office. The prices quoted for this task covers the cost of moving the safe. Any additional costs relating to structural work to strengthen floors has not been included.

4.2 Training

All but one surveyor had no previous experience in conducting surveys on Post Office premises. A one day training course for both ICL and POCL staff was conducted at ICL Kidsgrove. It was felt by both parties that with the amount of information to be conveyed, a 3 day training course would need to be undertaken by any Surveyor involved in the National Rollout.

To supplement the training given, the survey teams were accompanied for the first 3 days by managers from within both ICL Pathway and POCL, to ensure that the process was understood and adhered to.

Version: 1.0 Date: 2/03/98

Ref: IM/REP/029

4.3 Survey review

Every completed survey pack was reviewed on receipt and checked to ensure compliance to the ergonomic parameters. It was then categorised as detailed in the following section, and costings obtained from the following sources:

Work involved	Action
Joinery work	Referred to WTplc for quotation.
Screen modifications	Referred to POCL to cost screen parts.
	Referred to WTplc for labour quotation.
Relocating safes	Referred to POCL for quotation.
Relocating alarm circuits	Referred to POCL for quotation.
Electrical work	Costings supplied by WTplc

As the process used by the Surveyors for considering monitor and keyboard stands was based on the size of counter and did not consider the purchase price of the stand, the review also considered whether there was a more cost effective solution where stands were utilised. The prices quoted in this document reflect this reduction.

It should be noted that the estimates of joinery work were based on the narrative reports provided by the Surveyors. The actual prices quoted may have to be revised once a formal joinery survey is undertaken.

Ref: IM/REP/029 Version: 1.0

Date: 2/03/98

5. Results of the Survey

5.1 Outlet Categories

The results of the surveys have been broken down into the following categories:

- Category A offices which can be installed without any modifications.
- Category B offices that require the provision of items such as shelves and stands.
- Category C offices that require modifications to the counter, which includes screen, parcel hatch and joinery modifications.
- Category D offices where either no solution could be found or the proposed solution was unacceptable to the postmaster.

Category	Live Offices	New Offices	Total
A	1	2	3
В	23	10	33
С	42	4	46
D	14	4	18

5.2 Cost Breakdown

Preparation costs per office based on the number of counter positions are as follows:

No of Counters	No of Offices	Average Cost X (£) per office	Average Cost Y (£) per office
1	30	664.39	758.58
2	24	780.20	1,042.45
3	15	1,641.17	1,664.97
4	3	1,619.86	811.19
5	2	2,173.62	1,077.70
6	1	2,210.19	1,011.23
7	2	2,414.53	358.72
8	4	2,588.37	590.61
16	1	2,284.11	806.34

5.3 Stands

In addition to the shelves used to date, the survey also considered the following types of stands.

- 1. "Flipper" a combined monitor and keyboard stand which reduces the footprint by raising the monitor over the keyboard. Estimated cost £64.²
- 2. "Dublin" a combined monitor and keyboard stand which reduces the footprint by holding the keyboard under the screen in a sliding drawer. Estimated cost £76.
- 3. "Kidsgrove" a monitor stand which holds the monitor above the keyboard. The keyboard remains on the counter. Estimated cost £64.
- 4. "Hodnet" (keyboard) a keyboard shelf which allows the keyboard to extend over the edge of the counter. Estimated cost £19.
- 5. "Hodnet" (printer) similar to the keyboard version but designed to hold the counter printer over the edge of the counter. Estimated cost £18.

5.4 Utilisation of Stands

Category	No Used	No of Offices
Flipper	20	5
Dublin	75	26
Kidsgrove	0	0
Hodnet (Keyboard)	28	15
Hodnet (Printer)	4	4

It should be noted that stands were required in 50% of the offices visited. If these devices were not available the majority of offices would require major modification.

The Dublin stand proved popular in offices where extending the counter depth would obstruct the cash drawer. It must be noted however that the use of this stand could reduce the time taken to complete transactions as access to the drawer is restricted while the keyboard is being used and vica versa.

² The cost of a flipper stand has been estimated as the same price as a Kidsgrove stand. This is because the actual cost of the flipper stand would be based on the quantity ordered. There is a high tooling up cost of around £40,000. The cost of production is relatively inexpensive. A formal quotation will be obtained based on the result of this exercise.

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

6. No solution offices

There were 18 offices where no solution could be found to enable the Horizon system to be installed according to the ergonomic parameters. These are covered in detail in Appendix B and have been categorised into 4 groupings as follows:

- 1. SP counters This is the latest type of counter to be installed in offices. It is of a modular design and is intended to provide sufficient space for computer equipment. Deficiencies have however been identified in installation as follows:
 - It has been found that in some offices where space is limited, the modular unit between each serving position has not been fitted. This means that more serving positions can be accommodated, but there is little room to locate computer systems.
 - The depth of SP2000 counters has been set at 620mm to match the physical size of the keyboard and monitor. The operational depth of the keyboard and monitor with one directly in front of the other is 695mm. This means that unless sufficient width is available between serving positions a monitor stand will have to be employed to position the equipment. Even if sufficient width is available, its use can be constrained by the reach radius of 650mm from the centre of the serving position.
 - 2 offices had SP2000 counters installed at a height of 1030mm. With the depth restriction of 620mm a monitor stand was essential to extend the depth but due to the height limit of 1320mm the only possible solution was to use Hodnet keyboard stands. This would however have impeded access to cash drawers.
- 2. Ergonomics The ergonomics report stipulated maximum and minimum heights for positioning Horizon equipment. It also detailed the maximum distance that frequently used items should be from the user. There were 3 offices where the computer equipment could be positioned within the counter area if this restriction was increased to 695mm or extended beyond the current restriction of the edge of the counter.
 - 1 office could have been satisfied by the provision of flat screen monitors.
- **3.** Community Offices There were 2 offices within the sample where the Horizon equipment was located in the Living Room of a house. It has already been identified that separate guidelines need to be provided in these circumstances.

- **4. Unacceptable solutions** There were 8 offices where the proposed solution was unacceptable to the postmaster and alternative solutions could not be found without breaching the ergonomic constraints. The key issues which prevented agreement were:
 - Encroachment into personal space.
 - Encroachment into Retail space.
 - Insufficient space to cater for the number of serving positions being used.

7. Additional Options

7.1 Result of the review of additional options

The results of the review were as follows:

Option	Number of counters	Number of Offices
Flat screen monitor	15	10
Seats	0	0
Extended Reach	4	2
Expanded Reach	3	1
Self Inking Date Stamps	0	0

7.2 Flat Screen Monitor

The use of a touch screen monitor reduces the operational depth needed. Our suppliers have identified a monitor which reduces the depth from 365mm to 200mm. However this monitor is slightly higher and wider than the standard monitor.

Our review identified only 10 offices that would benefit from the use of the new monitor. At 3 of these offices, the only saving was the cost of using a Dublin stand.

The total savings for the 10 offices was £6,315.37 (See Appendix C)

Development costs and the purchase cost of the new monitors have not been included.

7.3 Seats

It was proposed that by using POCL approved seating the operators body could be raised to allows the centre of the monitor screen or the top of the operational height of

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

the equipment to be raised to 1410mm from the floor. (Without a chair the maximum height from the floor is 1320mm).

There were no offices which were found to benefit from this option. In the smaller offices there was insufficient space to locate a chair. In the larger offices, chairs were already provided or there was already sufficient counter space available.

7.4 Extending the Reach Parameters

The offices in question were no solution offices and as such the issues are detailed in section 6.

7.5 Expanding the Reach Parameters

This office was also a no solution office and is covered under section 6.

7.6 Self Inking Date Stamps

There were no occasions where the provision of self inking date stamps saved space as the postmaster would include these items in his working space area.

8. Other Findings

- In 9 of the 20 new offices the number of counter positions differed from the figures supplied. At 8 offices the requirement increased, at 1 it reduced. The net increase was 9 counters i.e. the total number of counters increased from 104 to 113.
- There was a large variation in the amount of working space demanded by certain postmasters. Unless a procedure is put in place to ensure that this is kept to a minimum, there could be a large number of screen alterations forced on us due to individual postmaster preferences.

Appendix A - Breakdown of items contained under each cost heading

Costs X	Costs Y	
Survey	TT Earthing <20m	
Standard Preparation	Earthing 20m-40m	
New Distribution Board	SWA Distribution Board >40m	
Henley Block	Electricity Board Tail Connection	
Earth Bonding <20m	Re-Survey Costs	
Earth Bonding 20-40m	Screen/Counter Modification - Parts	
Equipment Bonding - Counter	Screen/Counter Modification - Labour	
Shelf 0.5m x 0.5m	Drawer shortening	
Shelf 1m x 0.5m	Non Standard Shelving	
Image Monitor Stand	Alarm and Safe Relocation	
Scale Shelf - Secure Side	Non Standard Electrical Works	
Scale Clips		
Scale Shelf - Customer Side		
Grommet Hole Cover		
Monitor Stands		

NB.

Reapportionment of some costs may take place following joint discussions.

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

Appendix B - Category D Sites SPSO Counters

FAD Code	Outlet Name	Issue	
201328	Belford	SPSO 2000 counter. Insufficient space for 2 counter positions.	
324511	Warmley	New SPSO 2000 counter. 3 counter positions. Counter height 1030mm, depth 620mm. Equipment cannot be fitted within reach parameters. Possible solutions are to lower counter to enable monitor stands to be used, increase counter depth to enable equipment to fit front to back, or increase reach radius to 695mm.	
190504	Midsomer Norton	SPSO2000 counter. 4 counter positions. Counter height 1030mm, depth 600. Equipment could be positioned using Hodnet stands, but unacceptable to SPMR. Dublin stands would be accepted by SPMR but counter height would have to be lowered.	
175329	Benwell	4 counter position office but imminent change to an SPSO2000 counter with 3 counter positions. Insufficient space to accommodate 4 systems.	

Ergonomics

FAD Code	Outlet Name	Issue	
211328	Lesbury	Insufficient space for single counter position. SPMR will not permit encroachment into retail space. Extending the reach radius to allow the SPMR to turn to his left to operate the system would resolve the issue.	
175511	Brentry	Insufficient space for 3 counter positions. Standard counter with peninsular units at each position. Equipment could be fitted following extensive joinery work if the reach radius was extended beyond 180 degrees.	
245329	Grange Park	Insufficient space for 3 counter positions. Could be resolved by counter / screen modifications if reach radius was increased to 695mm.	
192503	Moorfields	Insufficient space for 3 counter positions. Counter / screen modifications would not improve the situation. Flat screen monitors would resolve.	

Community Offices

FAD Code	Outlet Name	Issue
173328	Netherwitton	Community Office. Equipment located in Living Room.
192328	West Duddo	Community Office. Equipment located in Living Room.

Unacceptable solutions

FAD Code	Outlet Name	Issue		
306329	Otterburn	Screen modifications could be undertaken but SPMR will not accept the counter printer being between the 2 speech units or any encroachment into his retail space.		
156504	Bathwick St	An acceptable location for the office printer could not be agreed as the SPMR's preferred location was higher than the maximum height. Space was available below the counter but could not be used as it was reserved for his dog.		
188328	Swarland	Counter / screen modifications could be undertaken but would encroach on retail space.		
240523	Westgate St	Counter / screen modifications could be undertaken. SPMR content with current layout but ergonomic parameters are being breached.		
206511	Danby House	Counter / screen modifications could be undertaken but SPMR will not accept the equipment being installed on the left hand side of the serving position.		
324523	Whitehall	Insufficient space for 2 counter positions. Counter / screen modifications would not improve the situation.		
254523	Primrose Hill	Insufficient space for 2 counter positions. Counter / screen modifications would not improve the situation.		
222511	Greystoke Ave	Multiple Outlet. Insufficient space for 4 counter positions. Representative of Dillons considering refurbishment.		

Ref: IM/REP/029 Version: 1.0 Date: 2/03/98

Appendix C - Potential cost savings of flat screen monitors

FAD Code	Outlet Name		No of counters	Saving (£)
217523	Painswick Ro	t	1	76.00
316523	North Woodchester		1	1,221.20
251523	Hempsted		1	1,011.69
206523	Minsterworth		1	107.00
276523	St Briavels		1	76.00
281523	Viney Hill		1	76.00
217328	Shilbottle		1	642.95
178328	Pegswood Colliery		2	1,937.63
314329	Prince Consort Rd		2	522.22
394329	Winlaton		4	644.68
	•	То	tal saving	£6,315.37